



NOTES:

- STAGGER ALL VERTICAL JOINTS BETWEEN ROCKS IN ADJACENT ROWS.
- SETBACK SHALL BE UNIFORM ON EACH ROW OF ROCKS.
- INSTALL ROCK FACE TO MATCH UPSTREAM AND DOWNSTREAM STONE WALLS.
- INSTALL 60' OF STACKED ROCK WALL, INCLUDING DOWNSTREAM CUTOFF.

SHEET NO. _____ OF _____

DRAWING NO. _____

CAD FILE NAME _____



LUZERNE COUNTY, PENNSYLVANIA

Stacked Rock Detail

DESIGNED	JEG	DATE	03/22
DRAWN	_____		_____
CHECKED	_____		_____
APPROVED	_____		_____
TITLE	_____		_____