

MARTY MURRAY

WASTE MANAGEMENT FACILITY

NRCS TAKES SAFETY VERY SERIOUSLY, HOWEVER, THE SAFETY COMMITMENT AND THE JOB SITE PRACTICES OF THE CONTRACTOR ARE BEYOND CONTROL OF NRCS. IT IS STRONGLY RECOMMENDED THAT SAFE WORKING CONDITIONS AND ACCIDENT PREVENTION PRACTICES BE THE TOP PRIORITY OF ANY JOB SITE. LOCAL, STATE, AND FEDERAL SAFETY AND HEALTH STANDARDS SHOULD ALWAYS BE FOLLOWED TO HELP INSURE WORKER SAFETY. MAKE CERTAIN ALL EMPLOYEES KNOW THE SAFEST AND MOST PRODUCTIVE WAY OF CONSTRUCTING THE DESIGNED PRACTICES. EMERGENCY PROCEDURES SHOULD BE KNOWN BY ALL EMPLOYEES. DAILY MEETINGS HIGHLIGHTING SAFETY PROCEDURES ARE ALSO RECOMMENDED. IT IS THE CONTRACTORS RESPONSIBILITY TO ENSURE A SAFE WORK ENVIRONMENT FOR THEIR EMPLOYEES.

THE HUA/MANURE STORAGE FACILITY IS NOT TO BE PUT INTO USE UNTIL A FINAL INSPECTION HAS BEEN CONDUCTED BY THE DESIGN ENGINEER. IF PUNCH LIST ITEMS ARE FOUND DURING THE INSPECTION THE ITEMS (IF ANY) ARE TO BE ADDRESSED/CORRECTED BY THE APPROPRIATE CONTRACTOR ACCORDING TO A PLAN PREPARED BY THE DESIGN ENGINEER. ONCE ALL ITEMS ARE CERTIFIED THE FACILITY CAN BE PUT INTO USE.

PROJECT LOCATION:
1904 WEST 8TH STREET
WYOMING, PA 18644

GENERAL NOTES

- FAILURE TO CONSTRUCT THIS FACILITY IN ACCORDANCE WITH THE NRCS DESIGN OR AUTHORIZED MODIFICATIONS WILL RESULT IN WITHDRAWAL OF NRCS TECHNICAL AND FINANCIAL ASSISTANCE.
- ALL FEDERAL, STATE, AND LOCAL LAWS, RULES, AND REGULATIONS GOVERNING THE CONSTRUCTION OF THIS FACILITY SHALL BE STRICTLY FOLLOWED. THE OWNER OR OPERATOR IS RESPONSIBLE FOR OBTAINING ALL CONSTRUCTION PERMITS.
- IT IS THE RESPONSIBILITY OF THE EXCAVATING CONTRACTOR TO COMPLY WITH PA ACT 187 (1996) AND ALL ITS REVISIONS BEFORE PERFORMING ANY EXCAVATION. THE PA ONE-CALL PHONE NUMBER IS 1-(800)-242-1776. THE SERIAL NUMBER FOR DESIGN IS 20191611939 DATED 6/10/2019.
- A MEETING BETWEEN THE LANDOWNER, CONTRACTOR, AND NRCS REPRESENTATIVE SHALL BE REQUIRED PRIOR TO ANY EXCAVATION OR CONSTRUCTION WORK.
- A COPY OF THE NRCS SPECIFICATIONS AND DRAWINGS SHALL BE ONSITE DURING ALL PHASES OF CONSTRUCTION. A COPY OF THE DRAWINGS SHALL BE PROVIDED TO THE TRUSS MANUFACTURER.
- OSHA REGULATIONS SHALL BE FOLLOWED AT ALL TIMES.
- THE CONTRACTOR IS RESPONSIBLE FOR IMPLEMENTING ALL MEASURES NECESSARY TO PROTECT WORK IN PROGRESS FROM ENVIRONMENTAL CONDITIONS SUCH AS TEMPERATURE EXTREMES, SURFACE, AND GROUND WATER.
- THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ACTUAL FIELD MEASUREMENTS SHOWN ON THE PLANS.
- IN THE EVENT ROCK, UNSTABLE SOILS, OR SEEPS ARE ENCOUNTERED DURING EXCAVATION, WORK SHALL BE STOPPED AND THE NRCS SHALL DETERMINE HOW TO PROCEED.
- THE CONTRACTOR IS RESPONSIBLE FOR THE SECURITY OF THE JOB SITE UNTIL THE WORK HAS BEEN CERTIFIED BY THE NRCS.
- CERTIFICATION OF CONFORMANCE SHALL CERTIFY THAT ALL WORK WAS PERFORMED TO THE NRCS SPECIFICATIONS.

CONSTRUCTION NOTES

- CLEAR AND GRUB THE ENTIRE AREA WITHIN THE WORK LIMITS.
- ALL FILL MATERIAL MUST NOT CONTAIN FROZEN MATERIAL, SOD, ROOTS, OR OTHER PERISHABLE MATERIAL, OR ROCK LARGER THAN EIGHT INCHES IN DIAMETER.
- SIX INCHES TOPSOIL WILL BE INCORPORATED INTO THE EARTHFILL TO MEET THE NEAT LINES SHOWN ON THE TYPICAL SECTION.
- ALL AREAS TOP-DRESSED WITH TOPSOIL AND DISTURBED DURING CONSTRUCTION WILL BE SEEDED ACCORDING TO NRCS CRITICAL AREA PLANTING SPECIFICATION.

INDEX OF DRAWINGS

- | | |
|--|-------------------------------------|
| 1. COVER SHEET | 30. 15" CURB DETAIL (SURCHARGE) |
| 2. E&S DETAILS | 31. 24" CURB DETAIL |
| 3. E&S PLAN VIEW 30 SCALE | 32. CONCRETE JOINT OPTIONS |
| 4. GENERAL CONSTRUCTION NOTES | 33. DETAIL SHEET |
| 5. CONCRETE CONSTRUCTION NOTES | 34. WELL DECOMMISSIONING |
| 6. ROOF CONSTRUCTION NOTES | 34a Well Underground Outlet Profile |
| 7. 40 SCALE PLAN VIEW | |
| 8. 30 SCALE PROFILE LOCATIONS PLAN VIEW | |
| 9. CONCRETE AND POST LAYOUT | |
| 10. TRUSS LAYOUT | |
| 11. NW BLDG. ELEVATION | |
| 12. SE BLDG. ELEVATION | |
| 13. SIDE ELEVATIONS | |
| 14. OPENING DETAIL | |
| 15. A-A PROFILE | |
| 16. B-B PROFILE | |
| 17. C-C & D-D PROFILES | |
| 18. E-E PROFILE | |
| 19. F-F & G-G PROFILES | |
| 20. FASTENER REQUIREMENTS 10' OVERHANG SIDE | |
| 21. FASTENER REQUIREMENTS 2' OVERHANG SIDE | |
| 22. WYE AND KNEE BRACE DETAIL SHEET | |
| 23. CORD AND DIAGONAL BRACING DETAIL SHEET | |
| 24. CROSS BRACING OPTIONS | |
| 25. ADDITIONAL BRACING | |
| 26. POST INSTALLATION DETAIL SHEET | |
| 27. K BRACE DETAIL SHEET | |
| 28. 5' HIGH, 8" THICK T-WALL (W/O SURCHARGE) | |
| 29. 5' HIGH, WALL CORNER DETAIL (W/O | |

TRUSS MANUFACTURER TO RECEIVE
DRAWINGS : 6, 9, 10, 11, 12

AS-BUILT/ DESIGN INFORMATION

QUALITY ASSURANCE STATEMENT				ENGINEER STATEMENT	
To the best of my knowledge, I certify that the practices have been installed as per the attached drawings and specifications, based on the information provided to me and/or observations I have made.				In my professional opinion, I certify that the practices have been installed as per the attached drawings and specifications, based on the information provided to me and/or observations I have made.	
Practice	Description	As-Built Quantity (By Inspector)	Inspector (Initials)	Certification (Engineer/JAA Signature)	Date Certified
342	CRITICAL AREA PLANTING				
313	MANURE STORAGE				
561	HEAVY USE AREA				
620	UNDERGROUND OUTLET				
558	ROOF RUNOFF				
367	ROOF				
382	FENCE				
575	TRAILS AND WALKWAY				
351	WELL DECOMMISSIONING				
500	OBSTRUCTION REMOVAL				
606	PERIMETER DRAIN				

DATE: 6/19
DESIGNED: Andy Beckwith
DRAWN: M. Murray
CHECKED: Andy Beckwith
APPROVED: 6/26/19


MARTY MURRAY
COVER SHEET



FILE NO.
DRAWING NO.
SHEET 1 OF 34

NORTHUMBERLAND COUNTY, PA


E&S POLLUTION CONTROL PLAN AND FINAL SEEDING RECOMMENDATIONS



FILTER SOCK

NOTES:

1. FILTER SOCK SHALL BE INSTALLED DOWN SLOPE OF THE DISTURBED AREAS OF THE CONSTRUCTION SITE.
2. TRAFFIC SHALL NOT BE PERMITTED TO CROSS FILTER SOCKS.
3. FILTER SOCK SHALL BE PLACED AT LEVEL EXISTING GRADE. BOTH ENDS OF THE SOCK SHALL BE EXTENDED AT LEAST 8' UP SLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT.
4. STAKES MAY BE INSTALLED IMMEDIATELY DOWN SLOPE OF THE SOCK IF SO SPECIFIED BY THE MANUFACTURER.
5. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES HALF THE ABOVE GROUND HEIGHT OF THE SOCK.
6. SOCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO THE MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24 HOURS OF INSPECTION.
7. BIODEGRADABLE FILTER SOCKS SHALL BE REPLACED AFTER 6 MONTHS; PHOTODEGRADABLE SOCKS AFTER 1 YEAR. POLYPROPYLENE SOCKS SHALL BE REPLACED ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.
8. UPON STABILIZATION OF THE AREA TRIBUTARY TO THE SOCK, STAKES SHALL BE REMOVED. THE SOCK MAY BE LEFT IN PLACE AND VEGETATED OR REMOVED. IN THE LATTER CASE, THE MESH SHALL BE CUT OPEN AND THE MULCH SPREAD AS A SOIL SUPPLEMENT.
9. ANY SECTION OF SILT FENCE WHICH HAS BEEN UNDERMINED OR TOPPED SHALL BE IMMEDIATELY REPLACED WITH A ROCK FILTER OUTLET.



SILT FENCE

NOTES:

1. SILT FENCE SHALL BE INSTALLED DOWN SLOPE OF THE DISTURBED AREAS OF THE CONSTRUCTION SITE.
2. SILT FENCE SHALL BE PLACED AT LEVEL EXISTING GRADE. BOTH ENDS OF THE FENCE SHALL BE EXTENDED AT LEAST 8' UP SLOPE AT 45 DEGREES TO THE MAIN FENCE ALIGNMENT.
3. FENCE SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED FENCE SHALL BE REPAIRED ACCORDING TO THE MANUFACTURER'S SPECIFICATIONS AND REPLACED WITHIN 24 HOURS OF INSPECTION.
4. SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH HALF THE ABOVE GROUND HEIGHT OF THE FENCE.
5. ANY SECTION OF SILT FENCE WHICH HAS BEEN UNDERMINED OR TOPPED SHALL BE IMMEDIATELY REPLACED WITH A ROCK FILTER OUTLET.
6. FENCE SHALL BE REMOVED AND PROPERLY DISPOSED OF WHEN TRIBUTARY AREA IS PERMANENTLY STABILIZED.

Seeding Recommendation

6. The seed mixture shall be the following or similar if approved by the NRCS representative.

Nurse Crop (required with every permanent seed application):

Oats	64 lbs/acre PLS
Wheat	90 lbs/acre PLS
Annual Rye	40 lbs/acre PLS


Permanent Stabilization:	
Perennial Rye	40 lbs/acre PLS
	PLUS
Tall Fescue	80 lbs/acre PLS

NOTE: This mixture is suitable for frequent mowing. Do not cut shorter than 4".

PLS means pure, live, seed. PLS is the product of the percentage of pure seed times percentage germination divided by 100. For example, to secure the actual planting rate for switchgrass, divide 12 lbs PLS by the PLS percentage shown on the seed tag. Thus, if the PLS content of a given seed lot is 35%, divide by .35 to obtain 34.4 lbs of seed, the amount of seed required to plant 1 acre. If partial completion of any part of the project is accomplished, and this area will be disturbed again BUT not for a period of 20 days or more, those areas must be seeded with a TEMPORARY cover-seeding.

Temporary Seed and mulch will be applied at the following rates:

Annual Ryegrass	40 lbs/Acre
Winter Rye	3 Bu/Acre
Winter Wheat	3 Bu/Acre
Spring Oats	3 Bu/Acre



STRAW BALE BARRIER

NOTES:

1. STRAW BALES SHALL BE INSTALLED ACROSS SWALES, WATERWAYS, AND DIVERSIONS WHERE SEDIMENT LADEN RUNOFF COULD LEAVE THE CONSTRUCTION SITE.
2. STRAW BALE BARRIERS SHALL NOT BE USED FOR PROJECTS EXTENDING MORE THAN 3 MONTHS.
3. STRAW BALE BARRIERS SHALL BE PLACED AT EXISTING LEVEL GRADE WITH ENDS TIGHTLY ABUTTING THE ADJACENT BALES. THE FIRST STAKE OF EACH BALE SHALL BE ANGLED TOWARD THE ADJACENT BALE TO DRAW THE BALES TOGETHER. STAKES SHALL BE DRIVEN FLUSH WITH THE TOP OF THE BALE. BOTH ENDS OF THE BARRIER SHALL BE EXTENDED AT LEAST 8' UP SLOPE AT 45 DEGREES TO THE MAIN BARRIER ALIGNMENT.
4. SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH ONE THIRD THE ABOVE GROUND HEIGHT OF THE BALE. DAMAGED OR DETERIORATED BALES SHALL BE REPLACED IMMEDIATELY UPON INSPECTION.
5. ANY SECTION OF THE STRAW BALE BARRIER WHICH HAS BEEN UNDERMINED OR TOPPED SHALL BE IMMEDIATELY REPLACES WITH A ROCK FILTER OUTLET.
6. BALES SHALL BE REMOVED WHEN THE TRIBUTARY AREA HAS BEEN PERMANENTLY STABILIZED.

THIS EROSION AND SEDIMENTATION PLAN IS BASED ON THE PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION EROSION AND SEDIMENT POLLUTION CONTROL PROGRAM MANUAL, TECHNICAL GUIDANCE NUMBER 363-2134-008, MARCH 2012.

Planting Recommendation

Seed can be applied with a drill or broadcast seeder. Band seeding is not permitted. If broadcast, harrow or disk lightly to cover seed. Roll with cultipacker or similar roller in same direction as seeding. (Double drilling gives better distribution of seeding and helps to spread the water while plants are small. Drill first lengthwise and then crosswise (in a zig-zag pattern). Optimum planting time is early spring or mid summer. 7. As soon as seeding is finished, mulch with 3 Tons/Acre of hay or straw, making a layer 1 to 1.5 inches deep. Set disk straight and go over mulch to press straw into the soil. Tackifiers can also be used for anchoring mulch.


1. When grading is finished, apply lime and fertilizer in accordance with soil test recommendations.
2. If soil test results are not available, apply 4 ton per acre of agricultural grade limestone and fertilize at the rate of 1,000 lbs. Of 10-20-20 or equivalent per acre.
3. Lime and one-half (1/2) the amount of the fertilizer shall be incorporated 4 to 6 inches into the soil.
4. Work area with chisel plow or similar type equipment, making sure lime and fertilizer are worked well into the soil.
5. Follow with the balance of fertilizer and seed.

Date _____
 Designed _____
 Drawn _____
 Checked _____
 Approved _____

MARTY MURRAY
 E&S DETAILS
 LUZERNE COUNTY, PENNSYLVANIA

United States Department of Agriculture
 USDA
 Natural Resources Conservation Service

File No. _____
 Drawing No. _____
 Sheet 2 of 34



General Site Permitting Information

- 1) Proposed area of disturbance is less than 1 Ac.
(Includes excavation, spoil pile, footer drain, etc...)
- 2) Name of Receiving Water Body: NONE_____
Stream Classification: NONE_____
Distance from Work Area to stream: GREATER THAN 1000FT
- 3) Are there any apparent wet lands within the project work area and/or receiving runoff from the area of disturbance? NO
- 4) Soil type(s) in area of disturbance:
Mardin channery silt loam.

Additional Notes:
Area of disturbance is 34,000 sq.ft.

--- Earth Disturbance Limits
 —□— Silt Fence
 □ Existing Structures
 () Soil Stockpiles:
 NONE

DESIGNED	DATE
DRAWN	
CHECKED	
APPROVED	

MARTY MURRAY
 E&S PLAN VIEW 40 SCALE
 LUZERNE COUNTY, PA



FILE NO.
DRAWING NO.
SHEET 3 OF 34

OWNER RESPONSIBILITIES

ACCESS

1. The owner is responsible for ensuring that all livestock are removed from the work site and that livestock will remain excluded from the work site until the project has received final certification and is approved for use.
2. The owner is to provide reasonable access to the work site.

EXCAVATION NOTES

GENERAL

3. **No excavation shall begin until the excavator has complied with all PA One-Call requirements and any utility company responses.**
4. All erosion and sedimentation practices shall be installed prior to beginning excavation.
5. **OSHA standards shall be followed for all excavation.**
6. Topsoil shall be stripped and stockpiled to be re-distributed when the project is complete.
7. All manure-laden soil shall be removed and spread according to the landowner's nutrient management plan.
8. The site shall be excavated until, good, stable soil is encountered.
9. If seeps are encountered in the excavation, provide clean 2B-stone backfill up to the seep elevation.
10. When hard material is encountered, over-excavate design sub-grade by 1.0' and replace with a compacted impermeable layer (i.e. CL/ML) before installing bedding stone; consult with design engineer before doing so.
11. If rock-refusal is met before the design sub-grade, changes in design elevations will require NRCS approval.
12. Excess material shall be disposed of as directed by the landowner and the NRCS inspector.
13. A uniform layer of 2B-stone (AASHTO #57), 3" thick shall be placed above subgrade to bed ALL concrete. Stone depth to be measured after compaction. Stone shall not be placed until earthen subgrade elevation and compaction is approved by NRCS inspector.
14. The contractor is responsible for protecting the construction site until the work has been completed and certified by the design engineer. This includes; dewatering the site as necessary as well as preventing upslope runoff from entering the work area. It is strongly recommended that all planned diversions or swales be installed first and all perimeter drain outlets be installed before stone or concrete is placed, if possible.
15. Final grading shall provide positive drainage away from all structures. Swales shall be shaped as necessary along the heavy use area and manure storage to direct stormwater away from the structures.

EARTHFILL

16. Earthen backfill shall be placed in a manner that prevents damage to the structures and allows the structures to assume the loads from the earth backfill gradually and uniformly. The height of the earth backfill adjacent to the structure shall be increased at the same rate on all sides of the structure.
17. Backfill shall be placed in even, horizontal layers. If necessary, over-excavate to an approximately level surface and build subgrade in evenly compacted, horizontal lifts of specified thickness.
18. Backfill shall be placed at optimum moisture content. Backfilled material shall have enough moisture so that when formed into a ball, it will not break if struck sharply with a pencil. Backfilling newly poured walls may not begin until 14-days after the final concrete placement. Compact using the following equipment and lift thickness:
 FOOTINGS AND STRUCTURE FLOOR:
 -(3) passes of sheepsfoot or vibratory roller in 6-inch lifts
 WITHIN 3 FEET OF WALLS:
 -(3) passes by hand compactor or small, manually directed plate vibrator in 6-inch lifts
 BEYOND 3-FEET OF WALLS:
 -(3) passes by track equipment (> 4,000 lbs) in 6-inch lifts
 -(4) passes by rubber tired equipment in 6-inch lifts
 -(3) passes vibratory roller in 6-inch lifts
19. Avoid backfill containing rocks or clods greater than 3" diameter, debris, roots, frozen soil, or other unsuitable material as determined by the NRCS inspector.

PIPES

20. All pipes shall meet minimum material specifications:
 - 20.1. SCH 40 PVC shall meet ASTM-D1785
 - 20.2. SDR-35 shall meet ASTM-D3034
 - 20.3. Corrugated polyethylene tubing shall meet ASTM-F405
21. All fittings shall be pressure-rated, watertight and meet minimum material specifications of pipe.
22. Pipes shall be installed to specified depth and to minimum design grade.
23. Trenches for pipelines shall be free of rocks and sharp-edged materials. A supply of AASHTO #57 bedding, or other suitable granular material, shall be available to bed pipelines in unstable soils or as directed by NRCS inspectors.
24. Pipes shall be backfilled as shown on design details. Any pipe to be placed in a traffic area is to be bedded as per design details and backfilled to the surface with 2A modified or 2RC aggregate. Any pipe not specifically detailed may be backfilled with moist earth, free of large clods or rocks, and hand compacted in 6-inch lifts. DO NOT drive machinery over recently backfilled pipes. Mound backfill 10% of trench depth to allow for settlement.

Date _____
 Designed _____
 Drawn _____
 Checked _____
 Approved _____

GENERAL CONSTRUCTION NOTES
 MARTY MURRAY
 LUZERNE COUNTY, PENNSYLVANIA



File No. _____

Drawing No. _____

Sheet 4 of 34

CONCRETE CONSTRUCTION NOTES

REINFORCEMENT

1. Reinforcing steel is to be Grade 60. Where 6"x6" w2.9xw2.9 (6 gage) is specified; the fabric shall be mats not rolls and supported on steel chairs. **NO CINDER OR CONCRETE BRICKS ARE PERMITTED.** Support shall be often enough so reinforcement stays at the required location within the slab or footing. A 5' chair spacing is a good starting point.
2. Form oil shall not be sprayed on any rebar, waterstop, or concrete.

CONCRETE

3. 4,000 psi 28-day compressive strength
4. MAXIMUM water-cement ratio 0.50
5. Air-content 5 to 7%, with air-entrainment
6. Max concrete temperature is 95°
7. Slump shall be 2 to 4 inches prior to addition of super-plasticizing admixtures being added, 3 to 6 inches without use of super-plasticizers.
8. Slump can be 7.5 inches MAX with super plasticizing admixtures added.
9. Concrete admixtures shall meet ASTM-C260 for air entrainment, and ASTM C494 type A, D, F or G for water-reduction and set-retardation and Types C or E for non-corrosive accelerators.
10. Admixtures shall be included in the design mix. Follow dosages and recommendations of manufacturer.
11. The contractor(s) shall provide a design mix to the NRCS for approval prior to ordering concrete. All load tickets shall be provided to and approved by the inspector on site and shall reflect all materials and quantities including admixtures, amount of water (metered water and free moisture in the aggregate), and total size of the batch. The batch ticket must indicate the amount of water than may be added on-site while maintaining the design requirements or no water may be added.

12. Concrete for curbs or walls shall not contain any SLAG in the mix.

PLACEMENT

13. **Concrete shall only be placed in the presence of an NRCS inspector.**
14. Placement during hot or cold weather will require a written plan in advance detailing concrete conditions, placement provisions, and a curing plan.
15. Concrete shall not be placed until the sub-grade, forms, and steel reinforcements have been inspected and approved by the NRCS. Notification shall be given far enough in advance to provide time for inspection.
16. No water in excess of the amount called for by the job design mix shall be added to the concrete. No water may be added after a superplasticizer.
17. Concrete shall be conveyed from the mixer to the forms as rapidly as practical by methods that will prevent segregation of the aggregates or loss of mortar. Concrete shall be placed within 1-1/2 hours after the introduction of cement to the aggregate unless an approved set-retarding admixture is used in the mix; during periods of hot weather, it may be necessary to reduce this time.

18. Concrete shall not be dropped more than 5 feet vertically. Superplasticized concrete shall not be dropped more than 12 feet vertically.
19. Formed walls shall be placed in 2' layers unless superplasticizer is used, in which case the maximum layer shall be 5'. Each layer shall be consolidated to ensure a good bond with the preceding layer.
20. Concrete shall be consolidated by vibrating immediately after placement and extend a minimum of 6" into the previously consolidated layer.
21. Concrete shall be worked into corners and angles and around all reinforcement and embedded items in a manner that prevents segregation or the formation of "honeycombing".
22. Vibration shall not be used to make concrete flow.
23. If the surface of a previously placed layer of concrete has taken a set to the degree that it will not mix with the preceding layer when vibrated, the contractor shall discontinue placing concrete and form a construction joint to avoid a "cold joint". **Vinyl waterstop and form material shall be on site prior to starting the placement of any concrete.**
24. The landowner has the option of having grooves floated or cut into the structure floor(s) for added traction for animals and equipment. This decision will be conveyed to the contractor(s) during price solicitation.

CURING

25. Concrete shall be allowed to cure at least 24 hours prior to beginning form or reinforcement placement for adjacent construction.
26. Heavy loads; skid loaders, pallets of forms, etc. shall remain off of concrete slabs or floors for a minimum of 3 days.
27. Forms for walls shall not be removed for at least 24 hours after placing the concrete. If forms are removed in less than 7 days, the exposed concrete shall be sprayed with curing compound.
28. Curing compound shall be applied in a uniform layer over all surfaces requiring protection at a rate as designated by the manufacturer. Curing compound shall be reapplied if disturbed within 3 hours after being applied.
29. All wall ties, honey-combing and air holes >3/4" shall be parged with non-shrink grout.
30. Random cracking in the walls and floor shall be evaluated and determined if the concrete needs removed or repaired. Removal and repair shall be the responsibility of the contractor at no increase in cost.
31. If major repairs are required, the contractor shall prepare a written repair plan with all materials and methods clearly stated and shall be approved by the NRCS engineer of authority before proceeding with the repair

JOINTS

32. Before new concrete is placed on or against concrete that has set, the surface of construction joints shall be cleaned of all laitance and debris by high-pressure water cutting, washing and wire-brushing, or as approved by engineer. The surface of the in place concrete shall be cut to expose clean, sound aggregate, but not so deep to undercut the edges of the large aggregate. All construction joints shall be wetted for at least 1-hour prior to new placement and standing water removed.
33. Slab control joints shall be saw-cut as soon as possible but no later than 24 hours after placement of the concrete, at the intervals indicated on the drawings. All joints shall be water tight and as shown on the detail drawings. The saw-cuts shall be thoroughly cleaned and dried so the sealant and primer will bond to the concrete.
34. For the joints in the drawings that call for an elastomeric sealant, the sealant shall meet the requirements stated in the Construction Specification, included in this design package, and shall also meet the following; The sealant shall be Type S (Single Component), Class 25, and meet the requirement for Type I (Able to be immersed in liquid). Some sealants require a primer be used before the sealant is installed; primers shall be used no matter if the joint is located in a "submerged" condition or not. It is recommended that the primer be supplied by the same manufacturer as the sealant, this will ensure that the sealant and primer are compatible.

TESTING REQUIREMENTS

35. ~~The contractor is responsible for obtaining a 3rd party ACI Certified Technician for field testing of concrete. The concrete plant can not test their own concrete. Slump, air entrainment, and concrete temperature shall be taken to ensure the concrete meets the NRCS requirements.
(4) concrete test cylinders shall be taken every 50 cu.yds.
(3) cylinders to be broke at 28 days and (1) cylinder shall be saved for a 56 day break if necessary; this shall be done for every 50 cu.yds sampled. Slump, air entrainment, and concrete temperature shall be recorded every 50 cu.yds as well.
All concrete for testing or making cylinders shall be taken from the discharge end of the pump truck.
All test results shall be provided to the inspector. The ACI technician shall be present from start of concrete placement until the last concrete truck leaves the site.~~
36. The contractor is responsible for ensuring that the concrete meets the design requirements. The contractor shall test the concrete as needed; slump, air entrainment, concrete temperature, and cylinders. All concrete for testing or making cylinders shall be taken from the discharge end of the pump truck. The NRCS, PACD, or Conservation District inspector may test the concrete as they feel the need to do so. The contractor is not to rely on the inspector to provide the testing service.

Date _____
Designed _____
Drawn _____
Checked _____
Approved _____

CONCRETE CONSTRUCTION NOTES
MARTY MURRAY
LUZERNE COUNTY, PENNSYLVANIA



File No. _____

Drawing No. _____

Sheet 5 of 34

Roof Structure Design & Construction Notes

- Trusses shall be used for this roof. Shop drawings shall be provided to the NRCS design engineer for approval prior to ordering the trusses and "PE" (Professional Engineer) sealed shop drawings shall be supplied by the Truss Plate Institute certified manufacturer at the time of truss delivery. (Truss and stringer configuration shown in the drawings is for illustration purposes only) NRCS does not design roof trusses.
 - * Make the truss designer aware of knee bracing being used.
 - * Make the truss designer aware trusses shall be designed for partially enclosed bldg.
 - * Make the truss designer aware trusses shall be design for Category II Importance factor.

- All nails used for structural connections shall be ring, spiral, or screw shank hardened nails full head size 16d or larger.
- All nails and bolts used with pressure treated wood shall be hot-dip galvanized nails that meet the minimum galvanized coating requirements for the most restrictive wood preservative treatment method. (i.e. CCA treated wood requires a minimum coating rating of G-90 however ACQ treated wood requires a coating rating of G-185. When the wood types are mixed, use the G-185 connectors. Consult with individual fastener, hardware manufacturer for recommendations)

CAUTION: New wood preservative treatment methods require special fasteners and connectors. All plates and fasteners used with ACQ, CBA or CA treatment formulas must conform to ASTM standards ASTM A153 for Hot-dip fasteners, and A653 for Hot-dip connector and sheet products. This change increases the galvanized coating requirements to a designation of G-185. Stainless steel fasteners and connections may be used in place of Hot-dip galvanized products.

- Nails for general framing can be common, full head size 16d or larger, smooth nails. General framing includes purlins, diagonal braces, lateral braces, etc.
- Bolts, screws, or metal plate connectors may be used instead of nails. Such substitutions shall provide a connection of equal or greater strength and durability, according to the National Forest Products Association's (NFPA) National Design Specification. Alternate connectors must be approved by the design engineer.
- All wood in contact with the ground or manure shall be pressure treated as per American Wood Preserver's Association Standard (posts shall be treated to 0.6 #/cu.ft. and all other wood shall be treated to 0.4 #/cu.ft.)
- All structural members which includes; All wye and knee bracing, bearing blocks, truss support blocks, and girders/headers; (excluding microlam girders/headers) shall be Southern Yellow Pine or Douglas Fir-Larch No. 2 Grade (Surface dry, used at 19% maximum moisture content).
All secondary members such as permanent or continuous bracing shall be (SYP) Southern Pine No. 3, (SPF) Spruce-Pine-Fir No. 2 or better.
Purlins shall be SYP No. 2, SPF No. 2, or better if spaced at 2' centers
Purlins shall be SYP No. 3 or better if spaced at 1.5' centers
- All posts are to be **fully pressure treated.**
Posts shall be 4 PLY 2"x8" GLU-LAM
HAVING THE FOLLOWING MIN. PROPERTIES:
Bending Fb = 2350 psi
Shear Fc = 2150 psi
E = 1700000 psi
- Galvanized angle iron (1/4" thick x 3" wide both ways) can be installed on the corners of the posts at entrance locations. Other means of post protection may be used if approved by the design engineer.

- Girders (depending on location)
Girders are to be (2) 1 3/4" X 9 1/4" 2.0E LVL'S
having the following min. properties:
1 3/4" x 9 1/4" 2.0E LVL'S
Bending Fb = 2900 psi
Moment = 6271 ft-lbs
Shear Fv = 3453lbs (320psi)
E = 2,000,000 psi


- HEADER
(1) 7" X 11 1/4" 2.0E PSL
having the following min. properties:
Bending Fb = 2900 psi
Moment = 35,940 ft-lbs
Shear Fv = 15,225lbs (320psi)
E = 2,000,000 psi

- Knee and Wye bracing are required for the posts and girders as shown. Wye bracing shall be installed AFTER all roof framing is complete. No Wye bracing shall be installed on the "inside" of the entrance locations.
- Permanent continuous lateral bracing is required, according to the truss MFG drawings. Continuous lateral bracing must be installed with staggered side by side overlap connections (no butt to butt connections).
The ends of the braces must extend fully past the truss and allow a 2-nail connection without using toenails.
- Permanent diagonal bracing is required at each end of the building and at intervals not to exceed what is shown in the drawings. All bracing shall be installed as Per the Truss Plate Institute BCSI-B3 and the detailed drawing.
- Roof fasteners shall be a combination of zinc coated steel and neoprene washer. Double stitch the seams of the roof edges. Typical aluminum roof shall have fasteners on a 9" spacing on the purlins 24" on center. Aluminum roofing shall have nominal thickness of 0.018 inches and coated steel of a 29 gauge minimum or better. Resolite panels may also be used as the roofing material. Fasteners for the Resolite panels shall be as recommended by the manufacturer. Painted steel, galvanized, or painted galvanized steel roofing to be discussed w/ landowner prior to bid solicitation. Galvalume roofing is not permitted for use.
- End trusses shall be faced with corrugated 29 gage galvanized steel roofing, an equivalent or better. Resolite panels may also be used.
The grade of Resolite panels shall be approved by the design engineer before ordering.
- Ventilation shall be provide by an overshot style ridge. Ventilation shall be provide to offer at least 2' of opening per 10' of building width.
- The roof area was designed to carry a combined loading of 40 psf. (DEAD + LIVE LOAD) on the entire roof surface and a uniform uplift of 14.5 psf under the entire roof.
"LIVE LOAD" is the ground snow load after reduction factors have been applied + wind load.
This roof is designed for (2) OPTIONAL enclosed side. All other sides shall remain "open"; major structural changes may be needed if any of "open" sides are enclosed. Consult with the design engineer if curtains or other means of siding is being considered.

DATE	_____
DESIGNED	_____
DRAWN	_____
CHECKED	_____
APPROVED	_____

MARTY MURRAY
ROOF NOTES
LUZERNE COUNTY, PA

United States Department of Agriculture  Natural Resources Conservation Service
FILE NO.
DRAWING NO.
SHEET 6 OF 34




DATE	_____
DESIGNED	_____
DRAWN	_____
CHECKED	_____
APPROVED	_____

MARTY MURRAY
40 SCALE PLAN VIEW

LUZERNE COUNTY, PA

 United States Department of Agriculture	Natural Resources Conservation Service
	FILE NO. _____ DRAWING NO. _____ SHEET 7 OF 34



DESIGNED	DATE
DRAWN	
CHECKED	
APPROVED	

MARTY MURRAY
30 SCALE PROFILE LOCATIONS
LUZERNE COUNTY, PA

United States
Department of
Agriculture





Natural Resources
Conservation Service

FILE NO.

DRAWING NO.

SHEET 8 OF 34



DATE _____

DESIGNED _____

DRAWN _____

CHECKED _____

APPROVED _____

MARTY MURRAY

CONCRETE AND POST LAYOUT

LUZERNE COUNTY, PA

United States
Department of
Agriculture

USDA


Natural Resources
Conservation Service

FILE NO.

DRAWING NO.

SHEET 9 OF 34

ALL TRUSSES 4' O.C
 ALL GIRDERS = 1 3/4" X 9 1/4" 2.0E LVL ATTACHED TO EACH SIDE OF POST AND SUPPORTED WITH BEARING BLOCKS.
 40 PSF COMBINED LOADING.
 CAT. II IMPORTANCE FACTOR, THERMAL FACTOR Ct = 1.2, EXPOSURE Ce = 1.0, PARTIALLY ENCLOSED BUILDING.
 ONLY THE SIDES LABELED AS ENCLOSED MAYBE ENCLOSED.
 ALL OTHER SIDES ARE TO REMAIN OPEN.
 GIRTS ARE TO BE SPF #1/#2 @ 18" SPACING.



20 SCALE


DESIGNED _____
 DRAWN _____
 CHECKED _____
 APPROVED _____
 DATE _____

MARTY MURRAY
 TRUSS AND GIRDER LAYOUT

LUZERNE COUNTY, PA

United States
 Department of
 Agriculture
USDA
 Natural Resources
 Conservation Service

FILE NO. _____
 DRAWING NO. _____
 SHEET 10 OF 34



DATE	
DESIGNED	
DRAWN	
CHECKED	
APPROVED	


MARTY MURRAY
 NORTHWEST BLDG ELEV.
 LUZERNE COUNTY, PA

United States Department of Agriculture
USDA
 Natural Resources Conservation Service

FILE NO.
 DRAWING NO.
 SHEET 11 OF 34

ENCLOSED GABLE END. GIRTS @ 18" O.C. SPACING NOT SHOWN

5 SCALE



DATE	
DESIGNED	
DRAWN	
CHECKED	
APPROVED	

MARTY MURRAY
SOUTHEAST BLDG. ELEV
LUZERNE COUNTY, PA

United States Department of Agriculture
Natural Resources Conservation Service


FILE NO.

DRAWING NO.


SHEET 12 OF 34

5 SCALE

NORTHEAST SIDE ELEVATION
OPEN SIDE (OUTSIDE LOOKING INTO BUILDING)



SOUTHWEST SIDE ELEVATION (OUTSIDE LOOKING INTO BUILDING)
ENCLOSED (STEEL) SIDE. GIRTS @ 18" O.C. SPACING NOT SHOWN.
NOTE: WYE BRACING SHOWN IS NOT REQUIRED IF STEEL SIDING WITH GIRTS @ 18" O.C. SPACING IS INSTALLED.



FEED PAD/ACCESS RD. NOT SHOWN

NO SCALE

DATE	
DESIGNED	
DRAWN	
CHECKED	
APPROVED	


MARTY MURRAY

SIDE ELEVATIONS

LUZERNE COUNTY, PA



FILE NO.	
DRAWING NO.	
SHEET 13 OF 34	




DATE	
DESIGNED	
DRAWN	
CHECKED	
APPROVED	

MARTY MURRAY
 OPENING DETAIL
 LUZERNE COUNTY, PA



FILE NO.	
DRAWING NO.	
SHEET	14 OF 34

4 SCALE



A-A PROFILE


DATE _____
 DESIGNED _____
 DRAWN _____
 CHECKED _____
 APPROVED _____

MARTY MURRAY
 A-A PROFILE

LUZERNE COUNTY, PA



FILE NO. _____
 DRAWING NO. _____
 SHEET 15 OF 34



B-B PROFILE


DATE	
DESIGNED	
DRAWN	
CHECKED	
APPROVED	

MARTY MURRAY
B-B PROFILE


LUZERNE COUNTY, PA



FILE NO.	
DRAWING NO.	
SHEET 16 OF 34	



C-C PROFILE



D-D (1) PROFILE

DATE _____
 DESIGNED _____
 DRAWN _____
 CHECKED _____
 APPROVED _____

MARTY MURRAY
 C-C & D-D PROFILES


LUZERNE COUNTY, PA

United States
 Department of
 Agriculture
USDA
 Natural Resources
 Conservation Service

FILE NO.

DRAWING NO.

SHEET 17 OF 34




E-E PROFILE


DESIGNED	DATE
DRAWN	
CHECKED	
PA APPROVED	

MARTY MURRAY
E-E PROFILE
LUZERNE COUNTY, PA

United States Department of Agriculture
USDA Natural Resources Conservation Service
 FILE NO.
 DRAWING NO.
 SHEET 18 OF 34



F-F PROFILE



G-G PROFILE

DATE	
DESIGNED	
DRAWN	
CHECKED	
APPROVED	

MARTY MURRAY
F-F, G-G PROFILE


LUZERNE COUNTY, PA




FILE NO.	
DRAWING NO.	
SHEET	19 OF 34

10FT OVERHANG SIDE
FASTENER REQUIREMENTS AT GIRDER & POST CONNECTIONS
1.75' X 9.25" 2.0E LVL GIRDERS



STAGGER BUTT JOINTS; NO POST SHALL HAVE A GIRDER BUTT JOINT ON BOTH SIDES



CONTINUOUS SPAN



TRUSS CONNECTION BETWEEN POSTS



DATE	
DESIGNED	
DRAWN	
CHECKED	
APPROVED	

LUZERNE COUNTY, PA


MARTY MURRAY
 FASTENER REQUIREMENTS
 10FT OVERHANG SIDE

United States
 Department of
 Agriculture
USDA
 Natural Resources
 Conservation Service


FILE NO.	
DRAWING NO.	
SHEET	20 OF 34

2FT OVERHANG SIDE
FASTENER REQUIREMENTS AT GIRDER & POST CONNECTIONS
1.75' X 9.25" 2.0E LVL GIRDERS


STAGGER BUTT JOINTS; NO POST SHALL HAVE A GIRDER BUTT JOINT ON BOTH SIDES




CONTINUOUS SPAN



NON-CONTINUOUS SPAN



TRUSS CONNECTION BETWEEN POSTS



DATE _____
 DESIGNED _____
 DRAWN _____
 CHECKED _____
 APPROVED _____

MARTY MURRAY
 FASTENER REQUIREMENTS
 2FT OVERHANG SIDE

LUZERNE COUNTY, PA


United States
 Department of
 Agriculture
USDA
 Natural Resources
 Conservation Service

FILE NO. _____

DRAWING NO. _____


SHEET **21** OF **34**

WYE AND KNEE BRACE DETAILS



BRACING DETAIL

GIRDER SUPPORT BLOCK IS REQUIRED BUT NOT SHOWN, FOR DRAWING CLARITY.



BRACING AT END OF BUILDING

BRACING DETAILS

1. Posts shall be notched to accommodate trusses. The notch shall be cut flush with the top of the girders, so the trusses sit on the notch and on top of both girders equally.
2. The truss support blocks, at locations between posts, can be notched sections of posts or 2x boards. Notches shall be cut, and the block positioned in the same fashion as the notches in the posts, described above.
3. The wye and knee braces shall be installed at a 45 degree angle from the treated posts. Install the wye braces after the trusses are set.
4. Drill pilot holes as needed to prevent splitting. Nails in split holes do not count towards connection.
5. Nails in contact with pressure-treated wood shall be galvanized.

*THE 16d POWER DRIVEN NAILS ARE BASED ON USING .131 DIAMETER X 3.25' LONG SPIRAL OR RING SHANK NAILS.

*THE 16d HAND DRIVEN NAILS ARE BASED ON USING .162 DIAMETER X 3.5' LONG SPIRAL OR RING SHANK NAILS.

*THE 20d HAND DRIVEN NAILS ARE BASED ON USING .192 DIAMETER X 4' LONG SPIRAL OR RING SHANK NAILS.

TABLE 2

*NUMBER OF NAILS REQUIRED			
BUILDING WIDTH (OVERHANG TO OVERHANG)			
JOINT	22.5' MAX (Tributary length)	27.5' MAX (Tributary length)	38' MAX (Tributary length)
Hand Driven 20d	A		9
Hand Driven 16d	B1		8
Hand Driven 16d	B2		8
Power Driven 16d	C		7
Power Driven 16d	D		4
Power Driven 16d	E		6
Power Driven 16d	F		5
Power Driven 16d	G		7
Power Driven 16d	H		4
Power Driven 16d	I		3
Power Driven 16d	J		7
Hand Driven 16d	K1		8
Hand Driven 16d	K2		8
Power Driven 16d	L		7

Hand Driven 20d
Hand Driven 16d
Hand Driven 16d
Power Driven 16d
Power Driven 16d
Power Driven 16d
Power Driven 16d
Power Driven 16d
Power Driven 16d
Power Driven 16d
Hand Driven 16d
Hand Driven 16d
Power Driven 16d


DATE _____
DESIGNED _____
DRAWN _____
CHECKED _____
APPROVED _____

MARTY MURRAY
WYE AND KNEE BRACING DETAIL SHEET
LUZERNE COUNTY, PA




FILE NO. _____
DRAWING NO. _____
SHEET 22 OF 34


CORD AND DIAGONAL BRACING




CONTINUOUS LATERAL BRACING ("RAT RUNS")
(2-16d NAILS @ EACH BRACE / TRUSS CONNECTION)



JOINTS IN CONTINUOUS LATERAL BRACES SHALL BE STAGGERED, SO THEY DO NOT LINE UP WITH THE NEXT TRUSS. AT A JOINT, EACH BOARD SHALL EXTEND FULLY PAST THE TRUSS, TO ALLOW FOR A TWO NAIL CONNECTION. THESE BRACES ARE AS PER TRUSS MFG. REQUIREMENTS, SHOWN ON THE TRUSS DESIGN.



DIAGONAL BRACING ON TOP SIDE OF BOTTOM CHORD
AT LOCATIONS SHOWN IN DRAWINGS
(2-16d NAILS @ EACH BRACE TRUSS CONNECTION)



DIAGONAL BRACING ON BOTTOM SIDE OF TOP CHORD
AT LOCATIONS SHOWN IN DRAWINGS
(2-16d NAILS @ EACH BRACE TRUSS CONNECTION)

DATE _____
DESIGNED _____
DRAWN _____
CHECKED _____
APPROVED _____

MARTY MURRAY
CORD AND DIAGONAL BRACING
LUZERNE COUNTY, PA


United States Department of Agriculture
USDA Natural Resources Conservation Service
FILE NO. _____
DRAWING NO. _____
SHEET 23 OF 34

CROSS BRACING

TO BE INSTALLED AT INTERVALS NOT TO EXCEED 20' ALONG CONTINUOUS LATERAL BRACING

CROSS BRACING IS REQUIRED ON TRUSS WEBS THAT HAVE A CONTINUOUS LATERAL BRACE OPTION #1

2X4 BLOCK OVER ALL BRACES




AT JOINT LOCATIONS; INSTALL LATERAL BRACE SO IT EXTENDS PAST TRUSS WEB MEMBER TO ENABLE A (2) NAIL CONNECTION TO THE WEB MEMBER

THE INSIDE CROSS BRACE SHALL CONNECT (3) OR (4) TRUSSES. THE OUTSIDE CROSS BRACE SHALL CONNECT (3) TRUSSES MINIMUM. ONLY (2) SHOWN HERE FOR DRAWING CLARITY. (2-16d NAILS @ EACH MEMBER/BLOCK)

THIS BRACE LOCATION IS SHOWN ON THE TRUSS DESIGN.

* ALL CROSS BRACES SHALL BE INSTALLED AT LESS THAN OR EQUAL TO 45 DEGREE ANGLES

CROSS BRACING IS REQUIRED ON TRUSS WEBS THAT HAVE A CONTINUOUS LATERAL BRACE OPTION #3




INSTALL "CONTINUOUS" CROSS BRACING ON THE OPPOSITE SIDE OF THE TRUSS WEB MEMBER AS THE LATERAL BRACE. THE CROSS BRACING MUST RUN THE ENTIRE LENGTH OF THE BUILDING ON THOSE WEB MEMBERS WITH LATERAL BRACING SPECIFIED IN THE TRUSS DESIGN AND AT OTHER LOCATIONS DICTATED BY THE BUILDING DESIGN ENGINEER. (2-16d NAILS @ EACH MEMBER)

* ALL CROSS BRACES SHALL BE INSTALLED AT LESS THAN OR EQUAL TO 45 DEGREE ANGLES

CROSS BRACING IS REQUIRED ON TRUSS WEBS THAT HAVE A CONTINUOUS LATERAL BRACE OPTION #2

2X4X12 BLOCK UNDER OUTSIDE BRACE



AT JOINT LOCATIONS; INSTALL LATERAL BRACE SO IT EXTENDS PAST TRUSS WEB MEMBER TO ENABLE A (2) NAIL CONNECTION TO THE WEB MEMBER


THE CROSS BRACE SHALL CONNECT AT LEAST (3) TRUSSES, (2-16d NAILS @ EACH MEMBER/BLOCK)

THIS BRACE LOCATION IS SHOWN ON THE TRUSS DESIGN.

* ALL CROSS BRACES SHALL BE INSTALLED AT LESS THAN OR EQUAL TO 45 DEGREE ANGLES

CROSS BRACING IS REQUIRED ON TRUSS WEBS THAT DO NOT HAVE A CONTINUOUS LATERAL BRACE; AT LOCATIONS SHOWN IN THE DRAWINGS.

OPTION #4



CROSS BRACING ON BOTH SIDES OF TRUSS WEBS AT LOCATIONS SHOWN WHERE THERE IS NOT A LATERAL BRACE (RAT RUN) LOCATED ON A TRUSS WEB MEMBER, DICTATED BY THE BUILDING DESIGN ENGINEER.

THE CROSS BRACE SHALL CONNECT AT LEAST (3) TRUSSES, (2-16d NAILS @ EACH MEMBER/BLOCK)


* ALL CROSS BRACES SHALL BE INSTALLED AT LESS THAN OR EQUAL TO 45 DEGREE ANGLES


DATE _____
DESIGNED _____
DRAWN _____
CHECKED _____
APPROVED _____

MARTY MURRAY
CROSS BRACING
LUZERNE COUNTY, PA

United States Department of Agriculture
USDA
Natural Resources Conservation Service

FILE NO. _____
DRAWING NO. _____
SHEET 24 OF 34



- CONTINUOUS LATERAL BRACING
AS PER TRUSS MFG. RECOMMENDATIONS
- TCD — TCD — TOP CHORD DIAGONAL BRACING
- BCD — BCD — BOTTOM CHORD DIAGONAL BRACING
-  WEB MEMBER CROSS BRACING

NOTES:

1. CONTINUOUS LATERAL BRACING SHOWN IS FOR A VISUAL REPRESENTATION ONLY; CONTINUOUS LATERAL BRACING LOCATIONS & SPACING ARE REQUIRED BY THE TRUSS MFG & SHOWN ON THE TRUSS DESIGN DRAWING.
2. ALL BRACING IS 2" X 4" GRADE MARKED LUMBER.
3. ALL CONNECTIONS SHOULD BE MADE WITH 2 - 16d NAILS. 2-16d NAILS. NO BUTT JOINTS.

"DRAWING IS NOT TO SCALE"

DATE _____
 DESIGNED _____
 DRAWN _____
 CHECKED _____
 APPROVED _____

MARTY MURRAY
 ADDITIONAL BRACING

LUZERNE COUNTY, PA




FILE NO.

DRAWING NO.

SINGLE POST ON WALL OR CURB INSTALLATION

ALL BRACKETS ARE TO BE ATTACHED TO TOP OF WALL OR CURB USING $\frac{5}{8}$ " DIA. X MIN. 4 $\frac{1}{2}$ " LENGTH SCREW TYPE ANCHORS. EXPANSION BOLTS ARE NOT PERMITTED.



STURDI-WALL SW84GL SERIES OR EQUIVALENT DRILL SET BRACKET ATTACHED TO TOP OF WALL OR CURB.

STURDI WALL SW80 CORNER SERIES OR EQUIVALENT DRILL SET BRACKET AT CORNER LOCATIONS.

STURDI WALL SW64GL SERIES OR EQUIVALENT DRILL SET BRACKET GABLE END POST LOCATIONS ONLY. NOTE: 4PLY 2"X6" GLULAM POST ARE ONLY USED AT THE GABLE END. ALL OTHER POST LOCATIONS ARE TO BE 4PLY 2"X8" GLULAM.

NOTE: BRACKETS, ANCHORS, AND POSTS CAN NOT BE INSTALLED UNTIL WALL OR CURB HAS CURED FOR MINIMUM OF 7 DAYS

DATE _____
 DESIGNED _____
 DRAWN _____
 CHECKED _____
 APPROVED _____


MARTY MURRAY
 POST INSTALLATION
 LUZERNE COUNTY, PA

United States Department of Agriculture
USDA
 Natural Resources Conservation Service

FILE NO. _____
 DRAWING NO. _____
 SHEET **26** OF **34**

"K" BRACING DETAIL

(FOR POSTS ON TOP OF CONCRETE WALL)



NOTES:

- 1). "K" bracing is needed when posts are anchored to top of walls.
- 2). Will need a "K" brace at the corners of the building.
A "K" brace should also be considered on both sides of openings.
- 3). Other "K" brace configurations may be used if approved by the designer.


** IF THE ENCLOSED SIDES ARE ENCLOSED WITH STEEL PANELS THEN "K" BRACES ARE NOT REQUIRED.
IF THE ENCLOSED SIDES ARE ENCLOSED WITH CURTAINS THEN "K" BRACES ARE REQUIRED.
IF ALL SIDES ARE LEFT OPEN THEN "K" BRACES ARE REQUIRED.

K-BRACE SHALL BE THE SAME SIZE AS THE SUPPORT POSTS. ORDER ENOUGH POSTS FOR K-BRACING.

"Not To Scale"

TYPICAL "K" BRACE LOCATION

UPPER END OF BRACE CAN BE INSTALLED BETWEEN HEADERS AND FASTENED WITH 16d NAILS IN ADDITION TO BOLTS THROUGH THE BRACE AND SUPPORT POST



INSTALL A BOLT THROUGH THE K-BRACE & POST-TO-WALL BRACKET. USE THE BOLT DIAMETER AS SPECIFIED BY THE BRACKET MANUFACTURER.


BOLT TO BE INSTALLED THROUGH PRE-DRILLED HOLE IN BRACKET. DO NOT DRILL ADDITIONAL HOLES THROUGH BRACKET.

Date: 7/10
 1/19
 Designed: JCD
 Drawn: JCD (REVISED)
 Checked: _____
 Approved by: _____

MARTY MURRAY
 LUZERNE
 K-BRACE DETAIL



File No.
 Drawing No.
 Sheet 27 of 34



ESTIMATED QUANTITIES

CONCRETE (0.27 CU.YDS./LIN.FT.)	_____	CU. YDS.
STEEL #4 (25.0 FT./LIN. FT.)	_____	FT.
STEEL #5 (3.60 FT./LIN.FT.)	_____	FT.
STEEL (42.5 FT./CORNER)	_____	FT.

- CONCRETE WILL MEET PA 313 OR 561 SPECIFICATION REQUIREMENTS.
- MINIMUM SPLICE LENGTH FOR ALL #4 BARS IS 16".
- MINIMUM SPLICE LENGTH FOR ALL #5 BARS IS 17".
- STEEL QUANTITY DOES NOT INCLUDE SPLICE LENGTHS.
- REBAR SHALL BE GRADE 60.

GENERAL DESIGN NOTES:


- DRAINAGE SHALL BE AWAY FROM THE WALL.
- THE MINIMUM TOP WIDTH OF THE BACKFILL AGAINST THE WALL SHALL BE EQUAL TO OR GREATER THAN THE BACKFILL HEIGHT.
- MAXIMUM FOOTING CONTACT PRESSURE IS 800 psf/ft.

DESIGN STRENGTHS: WORKING STRESS DESIGN

CONCRETE $f_c = 4,000$ psi STEEL $f_s = 24,000$ psi (GRADE 60)

WALL DESIGN LOADING: 313 STANDARD – LATERAL EARTH PRESSURE VALUES, SEE SECTION IV OF THE FIELD OFFICE TECHNICAL GUIDE.

- MANURE LOAD INSIDE = 65 psf/ft.
- SOIL BACKFILL LOAD OUTSIDE = 60 psf/ft. AND 85 psf/ft.
- NO HORIZONTAL SURCHARGE ADDED.
- SOIL BACKFILL DENSITY = 110 pcf.
- WATER TABLE MUST BE BELOW THE FOOTING ELEVATION



STEEL SCHEDULE

MARK	SIZE	TYPE	R	S	LENGTH
A	4	STR	---	---	4'-6"
B	4	STR	---	---	
C	5	2	2'-0"	1'-0"	3'-0"
D	4	STR	---	---	4'-9"
L	4	2	2'-0"	9"	2'-9"
L1	4	STR	---	---	4'-9"

NOTES:

1. FOR FROST PROTECTION, A 2-FOOT BACKFILL IS REQUIRED.
2. DIMENSIONS ARE TO THE REINFORCING BAR SURFACE.



ADAPTED AND MODIFIED FROM STANDARD DRAWING # PA-021C

Date	11/2018
Designed	
Drawn	BTU
Checked	
Approved by	

5' HIGH, 8" THICK T-WALL (W/O SURCHARGE)



File No.	PA-021C
Drawing No.	
Sheet	28 of 34



PLAN VIEW
WALL CORNER DETAIL

NOTES:


1. TIE LONG LEG OF MARK (L) CORNER BAR TO WALL SECTION T&S MARK (B) BAR AS SHOWN.
2. SHORT LEG OF MARK (L) BARS SHALL BE SUPPORTED WITH VERTICAL WALL SUPPORT BAR (L1).
3. 12 MARK (L) BARS PER CORNER. SEE APPROPRIATE WALL DRAWING FOR BAR DIMENSIONS AND QUANTITIES.
4. PLACE FIRST VERTICAL BAR (SEE PLAN VIEW) AT WALL CORNER, OR NO FARTHER THAN ONE-HALF THE VERTICAL BAR SPACING FROM THE CORNER.

ADAPTED AND MODIFIED FROM STANDARD DRAWING # PA-026A

ADAPTED AND MODIFIED FROM STANDARD DRAWING # PA-023

NOTES FOR FOOTING STEEL PLACEMENT

- 1.) FOOTING TEMPERATURE AND SHRINKAGE STEEL (T&S) TO BE EXTENDED INTO THIS REGION FROM BOTH SIDES OF CORNER. REGION IS OUTSIDE EXTENSION OF WALLS INCLUDING WALL THICKNESS.
- 2.) STRENGTH STEEL IS EXTENDED INTO THIS REGION FROM BOTH SIDES OF CORNER. REGION IS INSIDE EXTENSION OF THE WALLS. FOOTING SLAB T&S STEEL OUTSIDE THE CORNER REGION TO LAP SPLICE WITH THE STRENGTH STEEL 16 INCHES.
- 3.) IN BOTH CORNER REGIONS, STRENGTH STEEL AND T&S STEEL WILL REQUIRE SWITCHING POSITIONS FROM TOP TO BOTTOM AND VICE VERSA.



SLAB FOOTING CORNER DETAIL

NOTE: HOOK BARS USED FOR WALL SUPPORT NOT SHOWN IN THIS VIEW.

Date	11/2018
Designed	
Drawn	BTU
Checked	
Approved by	

5' WALL CORNER DETAILS (W/O SURCHARGE)




File No.	
Drawing No.	
Sheet	29 of 34

FEED PAD OR BACKFILL SIDE.
NOTE:
MAX BACKFILL HEIGHT = 6"
FROM TOP OF CURB

HEAVY USE
AREA SIDE

PERIMETER DRAIN IS
REQUIRED ALONG OUTSIDE
OF FOOTING. BOTTOM OF
PIPE TO BE AT OR BELOW
THE BOTTOM OF THE #57
STONE UNDER THE CURBING.
(DRAIN NOT SHOWN HERE
FOR DRAWING CLARITY)



C.J. = CONSTRUCTION JOINT
LIQUID TIGHT JOINT YES NO
LIQUID-TIGHT JOINT OPTIONS
= PVC 4" VINYL WATERSTOP

STEEL SCHEDULE				
MARK	SIZE	R	S	LENGTH
A	#4	-	-	3' 4"
B	#4	-	-	
C	#4	2'	2'	4'
L	#4	1' 7"	1' 8"	3' 3"

MIN. SPLICE LENGTH FOR ALL #4 BARS IS 16"
UNLESS OTHERWISE NOTED
LENGTHS SHOWN DO NOT INCLUDE BEND RADIUS

CONSTRUCTION JOINT OPTIONS
1. IF SLAB AND WALL ARE POURED
SEPARATELY, THE SLAB SURFACE MUST BE
THOROUGHLY CLEANED WITH WATER AND A
WIRE BRUSH. THE SURFACE OF THE JOINT
SHALL BE KEPT MOIST FOR AT LEAST 1
HOUR PRIOR TO PLACEMENT OF NEW
CONCRETE.

2. THE SLAB AND WALL MAY BE POURED AT
THE SAME TIME ELIMINATING THE NEED FOR
A CONSTRUCTION JOINT.

GENERAL DESIGN NOTES:
DRAINAGE SHALL BE AWAY FROM THE CURB.

DESIGN STRENGTHS:
CONCRETE = 4000 psi STEEL = GRADE 60

WATER TABLE MUST BE BELOW THE FOOTING ELEVATION

MIN. 3" AASHTO #57 (CLEAN STONE) REQUIRED UNDER FOOTING



STRENGTH STEEL REGION (SEE NOTE 2)

INSIDE FLOOR SLAB

FOOTING UNDER
MANURE

CURB

FOOTING UNDER
BACKFILL OR
FEED TABLE

NOTE:
HOOK BARS USED FOR WALL
SUPPORT NOT SHOWN IN THIS VIEW.


NOTES FOR FOOTING STEEL PLACEMENT

- 1.) FOOTING TEMPERATURE AND SHRINKAGE STEEL (T&S) TO BE EXTENDED INTO THIS REGION FROM BOTH SIDES OF CORNER. REGION IS OUTSIDE EXTENSION OF WALLS INCLUDING WALL THICKNESS.
- 2.) STRENGTH STEEL IS EXTENDED INTO THIS REGION FROM BOTH SIDES OF CORNER. REGION IS INSIDE EXTENSION OF THE WALLS. MIN. LAP SPLICE OF REBAR IS 16".
- 3.) IN BOTH CORNER REGIONS, STRENGTH STEEL AND T&S STEEL WILL REQUIRE SWITCHING POSITIONS FROM TOP TO BOTTOM AND VICE VERSA.

T & S BAR REGION (SEE NOTE 1)

SLAB FOOTING CORNER DETAIL

CURB CORNER DETAIL



DRAWING ADAPTED FROM PA STANDARD DRAWINGS#
018D, 020D, & 023 FOR POSTS ON CURB DESIGN

DATE	
DESIGNED	
DRAWN	
CHECKED	
APPROVED	

POST ON 15" CURB DETAIL

United States
Department of
Agriculture
USDA
Natural Resources
Conservation Service

FILE NO.


DRAWING NO.

SHEET 30 OF 34


LIQUID TIGHT SLAB JOINTS CROSS SECTIONS

(NOT TO SCALE)

JOINT 1




JOINT 2



CONSTRUCTION CONTROL

JOINT 3



LIQUID TIGHT SLAB/FLOOR JOINTS


GENERAL NOTES:

1. BACKER ROD SHALL BE A LARGER WIDTH THAN THE WIDTH OF THE SAW CUT.
2. SAW CUT OR JOINT FORMER IS ACCEPTABLE FOR JOINT 2.
3. SEALANT DEPTH SHALL BE 1/4" OR SLIGHTLY LESS THAN JOINT WIDTH, WHICHEVER IS LESS.
4. **CUT 50% OF THE REINFORCING STEEL DIRECTLY UNDER THE JOINT.**
5. USE JOINT 1 OR 2 FOR TWO POURS AND JOINT 3 FOR CONTINUOUS POURS.


LIQUID TIGHT WALL JOINTS PLAN VIEW

(NOT TO SCALE)


JOINT 4



JOINT 5



JOINT 6



LIQUID TIGHT WALL JOINTS

GENERAL NOTES:

1. **BE SURE TO CUT EVERY OTHER HORIZONTAL REINFORCING STEEL REBAR DIRECTLY AT THE JOINT.**
2. SEALANT DEPTH SHALL BE 1/4" OR SLIGHTLY LESS THAN JOINT WIDTH, WHICHEVER IS LESS.
3. USE JOINT 4 FOR TWO POURS AND JOINTS 5 OR 6 FOR CONTINUOUS POURS.

* Saw cut need not be greater than 1' for walls thicker than 8".

** Joint former or chamfer strip optional, Backer Rod and Elastomeric sealant needed in a saw cut joint or if a joint former is used. Elastomeric sealant needed if a chamfer strip is used. Cut and/or joint former or chamfer shall be on both sides of wall and across the top.


DATE _____
DESIGNED _____
DRAWN _____
CHECKED _____
APPROVED _____

MARTY MURRAY
CONCRETE JOINT OPTIONS
LUZERNE COUNTY, PA




FILE NO. _____
DRAWING NO. _____
SHEET 32 OF 34

REINFORCED CONCRETE DETAIL



- CONCRETE NOTES:
 1. CONCRETE SHALL BE 4000 PSI.
 2. STEEL SHALL BE GRADE 60.

**RAMP CURB DETAIL
(POURED WITH SLAB)**




- NOTES:
 1. CONCRETE TO BE 4000 PSI.
 2. DESIGN ADOPTED FROM PA-038.

**Access Road / ANIMAL WALKWAY Detail
(Typical)**



- Notes:
 1. Geotextile shall be Class II, Type A. Non-woven. Placement shall provide a one-foot (1') overlap between adjacent panels.
 2. Stone depth shall be measured after compaction.
 3. All stone shall be compacted with a smooth drum, vibratory roller.
 4. Surfacing material will be 2A modified.


Perimeter Drain Detail



PIPE USED FOR DRAINAGE TUBING SHALL BE PERFORATED CORRUGATED POLYETHYLENE, ASTM 405F. THE PIPE WILL OUTLET INTO SOLID SCH40 PVC ASTM D-1758 W/ MIN. OF 1% SLOPE.

4" DIAMETER DRAINAGE TUBING WITH A 2" DEPTH OF AASHTO #57 BEDDING BENEATH PIPE.


ROLL CURB DETAIL



- NOTES:
 1. CONCRETE TO BE 4000 PSI.
 2. BACKFILL TO SLOPE AWAY FROM SLAB.
 3. MINIMUM BACKFILL TO TOP OF SLAB.
 4. DESIGN ADOPTED FROM PA-038.

TRENCH DETAIL

TRENCHING SHALL BE IN ACCORDANCE WITH OSHA RECOMMENDATIONS



- NOTES:
 1. MATERIAL USED FOR INITIAL BACKFILL AND HAUNCHING SHALL HAVE A MAXIMUM SIZE OF 1.5 INCHES.
 2. INSTALL PIPE TO MANUFACTURERS RECOMMENDATIONS.
 3. COMPACT BACKFILL WITH VIBRATORY COMPACTOR WHEN IN VEHICULAR TRAFFIC AREAS.
 4. MAINTAIN A MINIMUM OF 30' OF COVER OVER TOP OF PIPE.
 5. BACKFILL TRENCH DAILY AND SLIGHTLY MOUND AT SURFACE TO ALLOW FOR SETTLEMENT. SEED WITH COVER CROP ASAP. DIRECT ANY POSSIBLE SURFACE WATER AWAY FROM THE WORK AREA.

INTENTIONALLY LEFT BLANK

DATE	
DESIGNED	
DRAWN	
CHECKED	
APPROVED	

MARTY MURRAY
DETAIL SHEET

LUZERNE COUNTY, PA

United States
Department of
Agriculture
USDA
Natural Resources
Conservation Service

FILE NO.
DRAWING NO.
SHEET 33 OF 34

SEE: WELL DECOMMISSIONING CONSTRUCTION SPECIFICATION PA351 FOR MATERIALS.

ORIGINAL GRADE. ELEVATION = 1322.5'

0.5FT. TOPSOIL CROWN SLIGHTY

NATURAL SOIL TO GROUND SURFACE AND CROWN SLIGHTLY. SEALING MATERIAL MAY BE SUBSTITUTED.

MIN. 1 FT. SEALING MATERIAL

NOTE: TOP 4' OF CASING MATERIAL REMOVED

SLIGHTLY COMPACTED NATURAL SOIL TO WITHIN 4 FT. OF SURFACE... SEALING MATERIAL MAY BE SUBSTITUTED.

2' SEALING MATERIAL. 1' ABOVE AND 1' BELOW STATIC WATER LEVEL.

STATIC WATER LEVEL. ELEVATION = 1320.7'

CLEAN FILL MATERIAL FROM BOTTOM OF WELL TO WITHIN 1' OF STATIC WATER LEVEL

EXISTING WELL CASING (STEEL/STONE OR WOOD CRIB CASING)

APPROXIMATE BOTTOM OF WELL ELEVATION = 1302.0'

APPROXIMATELY 6 FEET

NO SCALE

DATE	
DESIGNED	
DRAWN	
CHECKED	
APPROVED	


MARTY MURRAY
WELL DECOMMISSIONING
LUZERNE COUNTY, PA

United States Department of Agriculture
USDA
Natural Resources Conservation Service

FILE NO.

DRAWING NO.

SHEET 34 OF 34



Well Underground Outlet PROFILE

MARTY MURRAY
WELL UNDERGROUND OUTLET
PROFILE
LUZERNE COUNTY, PA



FILE NO.

DRAWING NO.

SHEET 34a OF 34

DESIGNED _____
DRAWN _____
CHECKED _____
APPROVED _____
DATE _____

APPROXIMATE DEPTH
OF WELL = 20.5'