

Bidding Clarifications – Barchik

Landowner specified a grooved finish floor and ramp

Contractors will include the drilling of a new well in their bid. The well drilling contractor will be responsible for electric to the well pump.

There will be no fencing on the access road. The animal trail and walkway will be fenced as well as the stream crossing. The stream crossing should include drop wires.

Contractors should include slant bar enclosures on the feed alley side.

The building will be three divided pens with double bowl waterers at each division.

Contractors should include geo fabric for under the access road as well as any wet spots in the animal trail and walkway in their bid.

Contractors will include all gates, slant bars and enclosures in their bid.

Bids must be sealed and titled “Barchik Ag BMP Project – Sealed Bid”

Bids are due by July 13, 2022 @ 3:00 p.m.